



[APC PB0-200](#)

Exam Name: APC NCPI Design

Q & A : 115 Q&As

Pdf Demo

Quality and Value for the PB0-200 Exam

[Just4Exams Practice Exams](#) for APC APC PB0-200 are written to the highest standards of technical accuracy, using only certified subject matter experts and published authors for development.

100% Guarantee to Pass Your PB0-200 Exam

If you do not pass the APC PB0-200 exam on your first attempt using our Just4Exams ***PB0-200 testing engine and pdf study guide***, we will give you a FULL REFUND of your purchasing fee.

Downloadable, Interactive PB0-200 Testing engines and PDF Version

Our Exam Preparation Material provides you everything you will need to take a [APC certification](#) examination. Details are researched and produced by [APC Certification](#) Experts who are constantly using industry experience to produce precise, and logical.

Free PB0-200 Exams:

This is demo only, this pdf do not include the questions and answers picture

Exam : APC PB0-200

Title : APC NCPI Design

1. A company has a 30kW N+1 InfraStruXure solution in their small data center. In the event of a power module failure, it wants e-mail notification that there is a loss of redundancy. The only connection is a LAN connection for monitoring. What should you do?

- A. using the InfraStruXure Manager, connect into the RJ45 port and configure the e-mail notification feature
- B. using an Out of Band Management Card, connect into an external modem and configure the e-mail notification feature
- C. using the serial port on the UPS, connect the UPS solution to a desktop computer and configure the e-mail notification feature
- D. using the Building Management Card, connect the UPS solution to the facility Building Management software and configure the e-mail notification feature

Answer: A

2. You have successfully completed an InfraStruXure solution using the BuildOut Tool. The client wants a complete system description including features and benefits. Which BuildOut Tool option provides this information?

- A. CTO Report
- B. Proposal Request
- C. Solution Information
- D. Detailed Quote Report

Answer: B

3. If a company requests that its UPS output power be distributed to the racks through an isolation transformer, what are they trying to do?

- A. decrease the cable size to the load
- B. increase the efficiency of the system
- C. increase availability throughout the data center
- D. prevent electrical noise from locking up the servers

Answer: D

4. A site requires redundant power feeds to single-corded servers. What is a possible redundant configuration?

- A. two single-module UPSs feeding one rack-mount Automatic Transfer Switch and one outlet strip per rack
- B. two single-module UPSs each feeding dual-panel distribution boards, which in turn feed two outlet strips per rack
- C. two single-module UPSs each feeding two outlet strips per rack; plugging half the servers in one strip and the other half in another strip
- D. two single-module UPSs each fed from separately derived utility sources; sources that come from one of two independent utility substations

Answer: A

5. Which two products are appropriate for an IT network wiring closet? (Choose two.)

- A. single-phase UPS
- B. 800 amp DC rectifier
- C. 4-post open frame rack
- D. 10kVA three-phase UPS
- E. 15-ton computer room air conditioner

Answer: AC

6. You are using the InfraStruXure BuildOut Tool. What information is needed to size an InfraStruXure UPS?

- A. Volts and Amps
- B. system redundancy
- C. total number of power modules
- D. Watts per rack and number of racks

Answer: D

7. A remote office for a small business has 20 employees. Its IT equipment supports four file servers, e-mail, storage, and Internet access. Which three products are appropriate for this office's IT room that has no IT staff? (Choose three.)

- A. 30kW N+1 UPS
- B. 12kVA N+1 UPS
- C. 4-post rack
- D. 15-ton computer room air conditioner
- E. remote security and environmental monitoring

Answer: BCE

8. How do you achieve full system redundancy in a precision air conditioning system?

- A. install multiple air conditioning systems in an N+1 configuration
- B. install a properly-sized DX air cooled unit with chilled water back-up
- C. install a properly-sized air conditioning unit with redundant compressors
- D. install Building System cooling (comfort cooling) with an air conditioning unit in standby

Answer: A

9. What is the most accurate way to determine the capacity of an existing standby generator?

- A. ask the facility manager
- B. calculate 30% over the UPS capacity
- C. look at the generator name plate in the genset room
- D. calculate capacity based on the load the generator is powering

Answer: C

10. What are two reasons why a fully rated UPS (output kW = output kVA) is more compatible with today's IT loads than an 80%-rated UPS (output kW = output kVA at a 0.8 power factor)? (Choose two.)

- A. 80%-rated UPSs are more efficient.
- B. Today's IT loads are power-factor corrected.
- C. Fully-rated UPSs have superior output voltage control.
- D. Fully-rated UPSs make it less likely to undersize the UPS.
- E. Today's IT loads lock up when powered by an 80%-rated UPS.

Answer: BD

11. A data center with raised-floor air distribution has hot spot problems in the equipment racks closest to the air conditioners. What are two possible solutions to this problem? (Choose two.)

- A. moving the racks closer to the air conditioners
- B. increasing airflow rate from the air conditioners
- C. moving the racks away from the air conditioners
- D. decreasing airflow rate from the air conditioners

Answer: CD

12. After your configuration is approved, your client requests changes that require you to modify the solution. Which BuildOut Tool option allows you to make changes to the approved solution and assigns a new solution ID?

- A. Save
- B. Save As
- C. Email Solution
- D. Submit Solution Review

Answer: B

13. A company has an existing data center where the temperature does not go below 27°Celsius (80°Fahrenheit). There are hot spots in the data center where the temperature is even higher. There is one 40kW chilled-water unit and 60kW of IT heat load in the space. The customer wants to reduce the temperature to 22°Celsius (72°Fahrenheit) and provide N+1 redundancy. What is the most reliable and cost-effective solution?

- A. add one 40kW chilled-water unit
- B. add two 60kW chilled-water units
- C. add two 40kW chilled-water units
- D. add one 40kW refrigerant-based unit
- E. add one 60kW refrigerant-based unit

Answer: C

14. You have specified that a 1000 VA rack-mount UPS solution be added to your client's existing data center. Considering the size of the UPS, which service product is appropriate?

- A. Load Bank
- B. Thermography
- C. Extended Warranty
- D. Preventive Maintenance

Answer: C

15. Within the Sizing Area section of the InfraStruXure BuildOut Tool, what is a "block"?

- A. a space allocated for cooling
- B. a rack position within the floor layout
- C. a rack position that allows power to cross
- D. a rack position that does not allow power to cross

Answer: D

16. A computer room is drawing 100 A as measured at the input electrical panel. The electrician does not know the room's power factor. The room requires UPS backup. Which UPS output rating ensures that the UPS is properly sized?

- A. kVA at a 0.7 output power factor
- B. kVA at a 0.8 output power factor
- C. kVA at a 0.9 output power factor
- D. kVA rated at a unity output power factor

Answer: D

17. Click the Calculator button. A medium-size data center has been retrofitted and the new IT equipment requires 39kW at a power factor 0.90. The existing UPS system is 40kVA. Which two actions should you take? (Choose two.)

- A. keep the actual UPS system: 40kVA means 40kW
- B. replace the diesel generator to cover the extra load
- C. replace the actual UPS system with a minimum 45kVA
- D. check the entire UPS installation to make sure it is able to support the new load

Answer: CD

18. An IT manager wants one hour of UPS runtime on a Voice over IP (VoIP) solution that will be located in a small wiring closet. To get the full hour of runtime and continuous operation, what else must be in place?

- A. The closet must have sufficient cooling for that period.
- B. Shutdown software should be loaded on the VoIP server.
- C. The UPS must be oversized in wattage to provide this runtime.
- D. The equipment must be installed in a full enclosure for proper security.

Answer: A

19. How do you identify the minimum runtime required for an IT environment that has different servers and operating systems running?

- A. by the number of operating systems running
- B. by the life of the specified batteries: 5 years or 10 years
- C. by the total power load (A longer runtime is needed as the load increases.)
- D. by identifying the longest shutdown time required by any of the operating systems

Answer: D

20. What is a common application for 2-post racks?

- A. telecom
- B. server room
- C. remote office
- D. IT data center

Answer: A

More [PB0-200 Braindumps](#) Information

Related PB0-200 Exams

PB0-200 DU0-001 PB0-100

Other APC Exams

PB0-100 DU0-001 PB0-200